
SITE DEVELOPMENT PLAN SET

TAX MAP 1 PARCEL 44

COMMERCIAL & INDUSTRIAL FLEX SPACE


BLANCH FARM ROAD
GREENVILLE, NEW HAMPSHIRE
APRIL 13, 2023



SHEET INDEX PAGE SHEET TITLE 1 CV-1 COVER SHEET 2 SP-1 SITE PLAN 3 EX-1 EXISTING CONDITIONS PLAN 4 GR-1 GRADING & EROSION CONTROL PLAN 5 UT-1 UTILITY & LANDSCAPING PLAN 6 LT-1 LIGHTING PLAN 7 DT-1 CONSTRUCTION DETAILS 8 DT-2 CONSTRUCTION DETAILS 9 DT-3 EROSION CONTROL DETAILS

PREPARED FOR AND LAND OF: DAVIS VILLAGE PROPERTIES, LLC

P.O. BOX 508 NEW IPSWICH, NH 03071



- THE LOCATION OF THE UTILITIES SHOWN ARE APPROXIMATE. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO LOCATE AND PRESERVE ALL UTILITY SERVICES.
- THE CONTRACTOR IS RESPONSIBLE FOR CONTACTING AND COORDINATING WITH ALL UTILITY COMPANIES AND JURISDICTIONAL AGENCIES PRIOR TO AND DURING CONSTRUCTION.
- 3. THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND PROPOSED WORK PRIOR TO CONSTRUCTION.


CONTACT DIG SAFE 72 HOURS PRIOR TO CONSTRUCTION

DIGSAFE.COM


I-888-DIG SAFE


1-888-344-7233








	APPRO	OVED BY	GREE	NVILLE	PLAN	INING	BOA	RD	
	ON: CHAIRMAN: VICE CHAIRMAN:				CERTIFIED BY AND				
		ang Pagangan an ang ang ang ang ang ang ang a	1447,2544,278 and 244,448,448,444,444	ron dag 1833 in pinu birgh Curi Masias,	d No. 2 State of Artista State Online State	पर मान मेहाहत गुरूपोर संगोदसंख्या स्थापन	*	tog (piper to 1 per la juris della specie)	
- REV.	– DATE		DES					- DR	
Park are the la-	003CV02.dwg	PROJ. NO.	1003.02	SHEET:	CV-1	PAGE	***************************************	1 OF · 9	














- 1. ALL CONSTRUCTION SHALL CONFORM TO THE APPLICABLE REQUIREMENTS AND SPECIFICATIONS OF THE
- 2. THE CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING THE LOCATION, SIZE, AND ELEVATION OF ALL EXISTING UTILITIES SHOWN OR NOT SHOWN ON THESE PLANS AND SHALL VERIFY THAT ALL THE INFORMATION SHOWN HEREON IS CONSISTENT, COMPLETE, ACCURATE, AND CAN BE CONSTRUCTED PRIOR TO AND/OR DURING CONSTRUCTION. FIELDSTONE LAND CONSULTANTS, PLLC, AS THE DESIGN ENGINEER, SHALL BE NOTIFIED IN WRITING OF ANY DISCREPANCIES, ERRORS, OMISSIONS, OR EXISTING UTILITIES FOUND INTERFERING WITH THE PROPOSED CONSTRUCTION SO THAT REMEDIAL ACTION MAY BE TAKEN BEFORE PROCEEDING WITH THE WORK.
- 3. THE CONTRACTOR SHALL CONTACT "DIGSAFE" 72 HOURS PRIOR TO THE START OF CONSTRUCTION (1-800-255-4977 IN NH, 1-888-344-7233 IN MA).
- 4. COMPLIANCE WITH ALL APPLICABLE REGULATIONS AND SPECIAL CONDITIONS OF TOWN/CITY AGENCIES, SUCH AS THE PLANNING BOARD, ZONING BOARD, CONSERVATION COMMISSION, AND OTHERS, IS MANDATORY AND IS THE RESPONSIBILITY OF THE OWNER.
- 5. ANY ALTERATION OF THIS DESIGN OR CHANGE DURING CONSTRUCTION MAY REQUIRE APPROVAL OF VARIOUS TOWN/CITY BOARDS OR AGENCIES AND SHALL BE DISCUSSED WITH THE OWNER AND FIELDSTONE LAND CONSULTANTS, PLLC PRIOR TO CONSTRUCTION.
- 6. THE CONTRACTOR IS RESPONSIBLE FOR CONTACTING THE APPROPRIATE TOWN DEPARTMENTS PRIOR TO CONSTRUCTION TO ARRANGE FOR NECESSARY INSPECTIONS:
- 7. THE CONTRACTOR IS RESPONSIBLE FOR MAINTAINING ACCURATE AS-BUILT INFORMATION OF ALL WORK, ESPECIALLY UNDERGROUND CONSTRUCTION OF UTILITY LINES, SERVICES, CONNECTIONS, ETC. AND APPROPRIATE TIES TO ABOVE GROUND PERMANENT STRUCTURES, FIELD SURVEY COORDINATES, OR SOME OTHER METHOD OF ESTABLISHING THE AS-BUILT CONDITION OF ALL CONSTRUCTION.


GENERAL CONSTRUCTION NOTES















2. INFRARED JOINT AFTER PLACING PAVEMENT.

SCALE: N.T.S. 3 PAVEMENT MATCH DT-1




SCALE: N.T.S.


DT - 1

TRAFFIC SIGNS - ON SITE

SCALE: N.T.S. TYPICAL UTILITY TRENCH

COMPANY REQUIREMENTS








(DIMENSIONS TO CENTER-LINE OF PAINTED LINES) MAXIMUM SLOPE IN ANY DIRECTION IS 2.0% FOR HANDICAP SPACES.

- 2. SEE SITE PLAN FOR LOCATION OF HANDICAP SPACES AND TYPE OF HANDICAP RAMP TO BE USED.
- 3. HANDICAP SYMBOL SHALL BE CENTERED ON WIDTH OF PARKING STALL AND LOCATED 6'6" FROM ACCESS DRIVE, INTO PARKING SPACE.
- 4. THE HANDICAP SYMBOL SHALL HAVE A 5' x 5' CONTRASTING BACKGROUND, NORMALLY BLUE. A BACKGROUND IS NOT REQUIRED IF WHITE OR YELLOW SYMBOL IS ON BLACK ASPHALT.

SCALE: N.T.S. PARKING STALL LAYOUT DT - 1







CONSTRUCTION DETAILS COMMERCIAL AND INDUSTRIAL FLEX SPACE

OR DIAL 8 1 1

CALL 811 - KNOW WHAT'S BELOW


TAX MAP 1 PARCEL 44 **BLANCH FARM ROAD** GREENVILLE, NEW HAMPSHIRE

PREPARED FOR AND LAND OF. DAVIS VILLAGE PROPERTIES, LLC

P.O. Box 508, New Ipswich, NH, 03071

SCALE: NONE APRIL 13, 2023 Surveying Φ Engineering Φ Land Planning Φ Permitting Φ Septic Designs FIELDSTONE LAND CONSULTANTS, PLLC 206 Elm Street, Milford, NH 03055

Phone: (603) 672-5456 Fax: (603) 413-5456 www. Fields to ne Land Consultants. comPROJ. NO. 1003.02 SHEET: PAGE NO. 7 OF 9



SEE DESIGN PLANS FOR DIMENSIONS
USE EROSION CONTROL BLANKETS ON SLOPES OVER 2:1 SLOPE

SCALE: N.T.S.

TYPICAL SWALE DETAIL W/ RIPRAP/ECB





	TABLE 1 (RECO	MMENDED	COVER)		TABLE 2 (RECOMMENT	DED TRENCH WIDTH)	
	LOCATION	PIPE	MINIMUM		INSIDE DIAMETER	TOTAL WIDTH	
		MATERIAL	COVER		12" TO 24"	I.D. + 24"	
	PAVED ROADS	ALL	3 FT.		OVER 24"	2 x l.D.	
	UNPAVED ROADS DRIVEWAYS UNPAVED AREAS	ALL ALL ALL	2 FT. 1 FT. 2 FT.				
						SCALE: N	1.T.S
	NIACE TOE	NICLIC	TVDIC	N I N			2
UKA.	INAGE TRE	INCH (IIPICA	┧ /			DT.





CULVERT	HEADWALL	HEADWALL	FILL	TOP	HEADWALL
DIAM.	LENGTH	HEIGHT	HEIGHT	HEIGHT	воттом
D	L	Н	FH	h	WIDTH W
INCHES		FEE	T & INCHES		
12	4'-3"	3'-9"	1'-1"	1'-3"	1'-11.25"
15	6'-0"	4'-3"	1'-7"	1'-6"	2'-0.75"
18	7'-0"	4'-6"	1'-10"	1'-6"	2'-1.50"
24	9'-0"	5'-0"	2'-4"	1'-6"	2'-3.00"
30	11'-0"	5'-6"	2'-10"	1'-6"	2'-4.50"
36	13'-0"	6'-0"	3'-4"	1'-6"	2'-6.00"
48	17'-9"	7'-3"	4'-7"	1'-9"	2'-9.75"


HEADWALL SHALL BE STEEL REINFORCED AND CONFORM TO NHDOT STANDARD SPECIFICATIONS


HEADWALL - PRECAST CONCRETE (OR EQUAL)

3
DT-2










LOCATION	BASIN OUTLETS		ELEVATIONS (FT.)							
	STAGE 1	STAGE 2	А	В	С	D	Ε	F	G	
OS1 (DP1)	3" ORIFICE	12" ORIFICE	866.0	866.0	868.1	869.3	865.0	870.0	863.0	
OS2 (DP2)	6" ORIFICE	12" ORIFICE	868.0	868.0	870.0	873.0	867.0	873.0	865.0	

SCALE: N.T.S.

STORMWATER BASIN OUTLET STRUCTURE OS 1

DT-





5. PROVIDE A MINIMUM OF 24" OF STRAIGHT COPPER AT SERVICE ENTRANCE INSIDE

OF BUILDING TO ALLOW FOR INSTALLATION OF ISOLATION VALVES, METER HORN AND METER, DUAL CHECK VALVE AND PRV (IF REQ'D).

6. WATER METER SHALL BE A $5/8 \times 3/4$ NEPTUNE METER, MEASURING CUBIC FEET, WITH A 2 BAND RADIO PRO—READ HEAD. THE RADIO READ SHALL BE MOUNTED ON THE STREET FACING SIDE OF THE STRUCTURE WITH WIRING BETWEEN THE UNIT AND THE METER.

SCALE: NONE

WATER SERVICE CONNECTION DETAILS

COMMERCIAL AND

6" - 12" CURVE

FROM HORIZONTAL IN HORIZONTAL PLANE

SCALE: N.T.S.

APRIL 13, 2023

8 DT-2

COMMERCIAL AND INDUSTRIAL FLEX SPACE

TAX MAP 1 PARCEL 44
BLANCH FARM ROAD
GREENVILLE, NEW HAMPSHIRE

PREPARED FOR AND LAND OF.

DAVIS VILLAGE PROPERTIES, LLC

P.O. Box 508, New Ipswich, NH, 03071

Surveying Φ Engineering Φ Land Planning Φ Permitting Φ Septic Designs



Phone: (603) 672–5456 Fax: (603) 413–5456 www.FieldstoneLandConsultants.com

DT02.dwg PROJ. NO. 1003.02 SHEET: DT-2 PAGE NO. 8 OF 9



- INSTALL STONE CHECK DAMS AND SILTATION CONTROL FENCES IN LOCATIONS SHOWN ON PLANS. EROSION AND SEDIMENTATION CONTROL MEASURES SHALL BE INSTALLED PRIOR TO
- 2. INSTALL STABILIZED CONSTRUCTION ENTRANCE(S).
- 3. CUT AND CLEAR TREES; DISPOSE OF DEBRIS. STUMPS ARE TO GROUND AND USED FOR EROSION CONTROL OR REMOVED FROM THE SITE AND DISPOSED OF PROPERLY.
- REMOVE TOPSOIL AND STOCKPILE AWAY FROM ANY WETLAND. STABILIZE STOCKPILE IMMEDIATELY BY SEEDING. PLACE SILT FENCE AROUND THE DOWN SLOPE SIDE OF EARTH STOCKPILES.
- ROUGH GRADE SITE CONSTRUCT DRAINAGE CULVERTS, BASINS AND SWALES DURING INITIAL PORTION OF CONSTRUCTION. STABILIZE IMMEDIATELY PER THE CONSTRUCTION AND EROSION CONTROL DETAILS. DO NOT DIRECT STORM WATER RUNOFF TO THESE STRUCTURES UNTIL A HEALTHY VEGETATIVE COVER IS ESTABLISHED.
- CONSTRUCT BUILDING, PAVED PARKING AREAS AND ASSOCIATED SITE IMPROVEMENTS AS SHOWN. ALL CUT AND FILL SLOPES SHALL BE STABILIZED UPON COMPLETION OF ROUGH GRADING PER THE THE EROSION CONTROL NOTES.
- 7. PLACE STONE CHECK DAMS AROUND INLETS AROUND ALL STRUCTURES UNTIL STORAGE FACILITIES AND PAVED AREAS ARE STABLE AND ALL NON-PAVED DISTURBED AREAS HAVE A HEALTHY VEGETATIVE COVER. SILT SACKS MAY BE UTILIZED IN PLACE OF STONE CHECK DAMS
- 8. INSPECT AND MAINTAIN EROSION CONTROL MEASURES ON A WEEKLY BASIS AND AFTER EVERY 0.25" OR GREATER RAINFALL.
- 9. DAILY, OR AS REQUIRED, CONSTRUCT TEMPORARY BERMS, CULVERTS, DITCHES, SILTATION FENCES, SEDIMENT TRAPS, ETC. MULCH AND SEED AS REQUIRED.
- 10. FINISH GRADING AND PREPARE FOR LOAMING. ALL DISTURBED AREAS SHALL BE STABILIZED WITHIN 72 HOURS AFTER FINAL GRADING.
- 11. FINISH CONSTRUCTING BUILDING AND PAVED/GRAVEL PARKING AREAS, PERMANENT SEEDING SHALL BE PERFORMED UPON COMPLETION OF PAVING, IF ANY (SEE EROSION CONTROL NOTES).
- COMPLETE PERMANENT SEEDING AND LANDSCAPING.
- 13. TEMPORARY EROSION CONTROL MEASURES SHALL BE REMOVED WHEN ALL DISTURBED AREAS HAVE BEEN STABILIZED.
- 14. STORMWATER FLOWS ARE NOT TO BE DIRECTED INTO THE DRAINAGE CULVERTS OR BASIN UNTIL THE CONTRIBUTING AREAS HAVE BEEN FULLY STABILIZED.
- ALL STRUCTURES SHALL BE CLEANED OF SEDIMENTS ONCE CONSTRUCTION IS COMPLETE.

CONSTRUCTION SEQUENCE NOTES

EROSION CONTROL (GENERAL CONSTRUCTION)

- 1. PRIOR TO STARTING ANY WORK ON THE SITE THE CONTRACTOR SHALL NOTIFY APPROPRIATE
- 2. EROSION CONTROL MEASURES SHALL BE INSTALLED PER PLANS AND DETAILS. PERIMETER CONTROLS SHALL BE IN PLACE PRIOR TO COMMENCEMENT OF EARTH DISTURBING ACTIVITIES.
- 3. EXISTING VEGETATION IS TO REMAIN UNDISTURBED WHEN POSSIBLE.
- EROSION AND SEDIMENTATION CONTROL MEASURES SHALL BE KEPT CLEAN DURING CONSTRUCTION. EROSION AND SEDIMENTATION CONTROL MEASURES SHALL BE INSPECTED AT LEAST ONCE A WEEK AND AFTER EVERY 0.25-INCH OR GREATER RAINFALL. SEDIMENTS SHALL BE DISPOSED OF IN AN UPLAND AREA THAT WILL NOT CONTRIBUTE TO SEDIMENT OFF-SITE AND BE PERMANENTLY
- 5. THE SMALLEST PRACTICAL AREA SHALL BE DISTURBED DURING CONSTRUCTION.
- 6. THE LAND AREA EXPOSED SHALL BE KEPT TO THE SHORTEST PRACTICAL PERIOD OF TIME. ALL NON-ACTIVE DISTURBED AREAS SHALL BE STABILIZED WITHIN 30 DAYS OF THE DISTURBANCE. ALL DISTURBED AREAS SHALL BE STABILIZED WITHIN 72 HOURS OF FINAL GRADING.
- 7. DITCHES, SWALES AND DRAINAGE BASINS SHALL BE CONSTRUCTED DURING THE INITIAL PHASE OF
- CONSTRUCTION AND STABILIZED PRIOR TO DIRECTING RUNOFF TO THEM. 8. AN AREA SHALL BE CONSIDERED STABILIZED IF ONE OF THE FOLLOWING HAS OCCURED:
 - BASE COURSE GRAVELS HAVE BEEN INSTALLED IN AREAS TO BE PAVED;
 - A MINIMUM OF 85% VEGETATED GROWTH HAS BEEN ESTABLISHED; A MINIMUM OF 3-INCHES OF NON-EROSIVE MATERIAL, SUCH AS STONE OR RIPRAP,
 - EROSION CONTROL BLANKETS HAVE BEEN PROPERLY INSTALLED.
- 9. EROSION CONTROL BLANKETS SHALL BE INSTALLED ON ALL SLOPES THAT ARE STEEPER THAN 3:1 (HORIZONTAL / VERTICAL). UNLESS OTHERWISE SPECIFIED THE CONTRACTOR SHALL USE NORTH AMERICAN GREEN SC150, OR APPROVED EQUAL
- 10. ALL AREAS RECIEVING EROSION CONTROL STONE OR RIPRAP SHALL HAVE A GEOTEXTILE MATERIAL INSTALLED BELOW THE STONE (SEE APPROPRIATE DETAILS).
- 11. ALL DISTURBED AREAS TO TURF FINSHED SHALL BE COVERED WITH A MINIMUM THICKNESS OF 4 INCHES OF COMPACTED LOAM. LOAM SHALL BE COVERED WITH THE APPROPRIATE SEED MIXTURE AS

PERMANENT SEED (LAWN AREAS)

POUNDS / 1,000 SQUARE FEET

CREEPING RED FESCUE PERENNIAL RYEGRASS KENTUCKY BLUEGRASS

0.92 LBS 1.15 LBS 0.58 LBS 0.12 LBS

APPLICATION RATE TOTALS 2.8 LBS PER 1,000 SF

12. APPLY LIMESTONE AND FERTILIZER ACCORDING TO SOIL TEST RECOMMENDATIONS. IF SOIL TESTING IS NOT FEASIBLE (CRITICAL TIME FRAMES OR VARIABLE SITES) THEN APPLY FERTILIZER AT A RATE OF 11 POUNDS PER 1,000 SF AND LIMESTONE AT A RATE OF 90 POUNDS PER 1,000 SF. FERTILIZER SHALL BE LOW PHOSPHATE (LESS THAN 2% PHOSPHORUS).

CAUTION SHOULD BE TAKE WHEN THE PROPERTY IS LOCATED WITHIN 250 FEET OF A WATER BODY. IN THIS CASE ALL FERTILIZERS SHALL BE RESTRICTED TO A LOW PHOSPHATE. SLOW RELEASE NITROGEN FERTILIZER. SLOW RELEASE FERTILIZERS MUST BE AT LEAST 50% SLOW RELEASE NITROGEN COMPONENT. NO FERTILIZER EXCEPT LIMESTONE SHALL BE APPLIED WITHIN 25 FEET OF THE SURFACE WATER. THESE ARE REGULATED LIMITATIONS.


- 13. PERMANENT OR TEMPORARY COVER MUST BE IN PLACE BEFORE THE GROWING SEASON ENDS (SEE WINTER CONSTRUCTION NOTES). NO DISTURBED AREAS SHALL BE LEFT EXPOSED DURING THE
- 14. A VIGOROUS DUST CONTROL PROGRAM SHALL BE APPLIED BY THE SITE CONTRACTOR. DUST SHALL BE MANAGED THROUGH THE USE OF WATER AND/OR CALCIUM CHLORIDE.
- 15. IN NO WAY ARE THE MEASURES INDICATED ON THE PLANS OR IN THESE NOTES TO BE CONSIDERED ALL INCLUSIVE. THE CONTRACTOR SHALL USE JUDGEMENT TO INSTALL ADDITIONAL EROSION CONTROL MEASURES AS SITE CONDITIONS, WEATHER OR CONSTRUCTION METHODS WARRANT.
- 16. FOLLOWING PERMANENT STABILIZATION, TEMPORARY EROSION CONTROL MEASURES SHALL BE REMOVED AND ACCUMULATED SEDIMENTATION IS TO BE DISPOSED OF IN AN APPROVED LOCATION, OUTSIDE OF JURISDICTIONAL WETLANDS.

EROSION CONTROL (WINTER CONSTRUCTION)


- 1. ALL PROPOSED VEGETATED AREAS WHICH DO NOT EXHIBIT A MINIMUM OF 85% VEGETATED GROWTH BY OCTOBER 15TH, OR WHICH ARE DISTURBED AFTER OCTOBER 15TH, SHALL BE STABILIZED. STABILIZATION METHODS SHALL INCLUDE SEEDING AND INSTALLING EROSION CONTROL BLANKETS ON SLOPES GREATER THAN 3:1, AND SEEDING AND PLACING 3 TO 4 TONS OF MULCH PER ACRE. SECURED WITH ANCHORED NETTING, ELSEWHERE. THE INSTALLATION OF EROSION CONTROL BLANKETS OR MULCH AND NETTING SHALL NOT OCCUR OVER ACCUMULATED SNOW OR FROZEN GROUND AND SHALL BE COMPLETED IN ADVANCE OF THAW OR SPRING MELT EVENTS.
- 2. ALL DITCHES OR SWALES WHICH DO NOT EXHIBIT A MINIMUM OF 85% VEGETATED GROWTH BY OCTOBER 15TH, OR WHICH ARE DISTURBED AFTER OCTOBER 15TH, SHALL BE STABILIZED WITH STONE OR EROSION CONTROL BLANKETS APPROPRIATE FOR THE DESIGN FLOW CONDITIONS.
- 3. AFTER NOVEMBER 15TH, INCOMPLETE ROAD OR PARKING SURFACES, WHERE WORK HAS STOPPED FOR THE WINTER SEASON, SHALL BE PROTECTED WITH A MINIMUM OF 3 INCHES OF CRUSHED GRAVEL OR PROPERLY INSTALLED EROSION CONTROL BLANKETS COVERED WITH HAY, OTHER STABILIZATION OPTIONS ARE TO BE APPROVED BY THE APPROPRIATE AGENCIES AND THE DESIGN ENGINEER. IF CONSTRUCTION IS TO CONTINUE THROUGH THE WINTER MONTHS THEN THE ROAD SHOULD BE CLEARED OF ACCUMULATED SNOW AFTER EACH STORM EVENT

EROSION CONTROL NOTES







VIEW LOOKING UPSTREAM



PROFILE - CHECK DAM SPACING


- 1. STONE CHECK DAMS SHOULD BE INSTALLED BEFORE RUNOFF IS DIRECTED TO THE SWALE OR DRAINAGE DITCH.
- 2. THE MAXIMUM CONTRIBUTING DRAINAGE AREA TO THE CHECK DAM SHOULD BE LESS THAN ONE ACRE.
- STONE CHECK DAMS SHOULD NOT BE USED IN A FLOWING STREAM.
- STONE CHECK DAMS SHOULD BE CONSTRUCTED OF WELL-GRADED ANGULAR 2 TO 3 INCH STONE. THE INSTALLATION OF 3/4-INCH STONE ON THE UPGRADIENT FACE IS RECOMMENDED FOR BETTER
- 5. WHEN INSTALLING STONE CHECK DAMS THE CONTRACTOR SHALL KEY THE STONE INTO THE CHANNEL BANKS AND EXTEND THE STONE BEYOND THE ABUTMENTS A MINIMUM OF 18-INCHES TO PREVENT
- 6. STONE CHECK DAMS SHOULD BE REMOVED ONCE THE SWALE OR DITCH HAS BEEN STABILIZED UNLESS OTHERWISE SPECIFIED.






- 1. SILT FENCES SHOULD NOT BE USED ACROSS STREAMS, CHANNELS, SWALES, DITCHES OR OTHER
- 2. SILT FENCE SHOULD BE INSTALLED FOLLOWING THE CONTOUR OF THE LAND AS CLOSELY AS POSSIBLE AND THE ENDS OF THE SILT FENCE SHOULD BE FLARED UPSLOPE.
- 3. IF THE SITE CONDITIONS INCLUDE FROZEN GROUND, LEDGE OR THE PRESENCE OF HEAVY ROOTS THE BASE OF THE FABRIC SHOULD BE EMBEDDED WITH A MINIMUM THICKNESS OF 8 INCHES OF 3/4-INCH
- 4. SILT FENCES PLACED AT THE TOE OF SLOPES SHOULD BE INSTALLED AT LEAST 6 FEET FROM THE TOE TO ALLOW SPACE FOR SHALLOW PONDING AND ACCESS FOR MAINTENANCE.
- 5. THE MAXIMUM SLOPE ABOVE THE FENCE SHOULD BE 2:1 AND THE MAXIMUM LENGTH OF SLOPE ABOVE
- 6. REMOVED SEDIMENT SHALL BE DEPOSITED TO AN AREA THAT WILL NOT CONTRIBUTE TO SEDIMENT OFF-SITE AND CAN BE PERMANENTLY STABILIZED.
- 7. SILT FENCES SHOULD BE REMOVED WHEN THE UPSLOPE AREAS HAVE BEEN PERMANENTLY STABILIZED.


SCALE: N.T.S. SILT FENCE





- 1. DIMENSIONS GIVEN IN THIS DETAIL ARE EXAMPLES: DEVICE SHOULD BE INSTALLED PER MANUFACTURER'S
- 2. INSTALL STRAW/COCONUT FIBER EROSION CONTROL MAT SUCH AS NORTH AMERICAN GREEN SC150 OR EQUAL ON ALL SLOPES EXCEEDING 3' HORZ: 1' VERT.
- 3. THE EROSION CONTROL MATERIAL(S) SHALL BE ANCHORED WITH "U" SHAPED 11 GAUGE WIRE STAPLES OR WOODEN STAKES WITH A MINIMUM TOP WIDTH OF 1 INCH AND LENGTH OF 7 INCH.
- 4. SLOPE SURFACE SHALL BE FREE OF ROCKS, CLODS, STICKS AND GRASS. MATS / BLANKETS SHALL HAVE GOOD SOIL CONTACT.
- 5. APPLY LIME, FERTILIZER AND PERMANENT SEEDING BEFORE PLACING BLANKETS.
- 6. BEGIN AT THE TOP OF THE SLOPE BY ANCHORING THE BLANKET AS SHOWN. ROLL THE BLANKETS DOWN THE SLOPE. ALL BLANKETS MUST BE SECURELY FASTENED TO SOIL SURFACE BY PLACING STAPLES OR STAKES IN APPROPRIATE LOCATIONS. REFER TO MANUFACTURERS STAPLE GUIDE FOR CORRECT STAPLE
- 7. LAY BLANKETS LOOSELY AND STAKE OR STAPLE TO MAINTAIN DIRECT CONTACT WITH THE SOIL. DO NOT
- 8. IN LOOSE SOIL CONDITIONS THE USE OF STAPLES OR STAKE LENGTHS GREATER THAN 6 INCHES MAY BE NECESSARY TO PROPERLY SECURE THE BLANKETS.
- 9. THE CONTRACTOR SHALL MAINTAIN THE BLANKET UNTIL ALL WORK ON THE CONTRACT HAS BEEN COMPLETED AND ACCEPTED. MAINTENANCE SHALL CONSIST OF THE REPAIR OF AREAS WHERE DAMAGED BY ANY CAUSE. ALL DAMAGED AREAS SHALL BE REPAIRED TO REESTABLISH THE CONDITIONS AND GRADE OF THE SOIL PRIOR TO APPLICATION OF THE COVERING AND SHALL BE REFERTILIZED, RESEEDED AND REMULCHED AS DIRECTED.

SCALE: N.T.S. EROSION BLANKETS - SLOPE INSTALLATION




- INSTALL AND MAINTAIN SACKS IN ALL CATCH BASINS.
- 2. TO INSTALL SACK, REMOVE CATCH BASIN GRATE AND PLACE SACK IN OPENING, HOLD OUT APPROXIMATELY SIX INCHES OF THE SACK OUTSIDE THE FRAME FOR THE LIFTING STRAPS. REPLACE THE GRATE TO HOLD THE
- 3. THE SACK SHOULD BE INSPECTED AFTER EVERY STORM, OR ONCE EVERY TWO WEEKS, WHICH EVER OCCURS FIRST.
- 4. THE RESTRAINT CORD SHOULD BE VISIBLE AT ALL TIMES. IF THE CORD IS COVERED WITH SEDIMENT, THE SACK SHOULD BE EMPTIED. EMPTY THE SACK AWAY FROM THE CATCH BASIN TO PREVENT SEDIMENT FROM RE-ENTERING THE CATCH BASIN, EMPTY THE SACK PER THE MANUFACTURES RECOMMENDATIONS.
- 5. REPLACE THE SACK IN THE CATCH BASIN AFTER THE SACK HAS BEEN EMPTIED. ONCE CONSTRUCTION IS COMPLETE AND ALL DISTURBED AREAS HAVE BEEN STABILIZED BY PAVING OR A HEALTHY VEGETATIVE COVER. REMOVE THE SACK FROM THE CATCH BASINS.

SCALE: N.T.S.

SILT SACK SEDIMENT FILTER





DIVERSION RIDGE REQUIRED

WHERE GRADE EXCEEDS 2%

- 3" - 6" BERM

ROADWAY

2% OR GREATER

FILTER FABRIC

NOTES:

1. THE ENTRANCE SHALL BE MAINTAINED IN A CONDITION THAT WILL PREVENT TRACKING OR FLOWING OF SEDIMENT ONTO PUBLIC RIGHT-OF-WAYS. THIS MAY REQUIRE TOP DRESSING, REPAIR AND/OR CLEANOUT OF ANY MEASURES USED TO TRAP SEDIMENT.

<u>PLAN VIEW</u>

- 2. THE MINIMUM STONE USED SHOULD BE 3-INCH CRUSHED STONE.
- 3. THE MINIMUM LENGTH OF THE PAD SHOULD BE 75 FEET, EXCEPT THAT THE MINIMUM LENTH MAY BE REDUCED TO 50 FEET IF A 3-INCH TO 6-INCH HIGH BERM IS INSTALLED AND THE ENTRANCE OF THE PROJET SITE.
- 4. THE PAD SHOULD EXTEND THE FULL WIDTH OF THE CONSTRUCTION ACCESS ROAD OR 10 FEET, WHICHEVER IS GREATER.
- 5. THE PAD SHOULD SLOPE AWAY FROM THE EXISTING ROADWAY.
- 6. THE PAD SHOULD BE AT LEAST 6-INCHES THICK.
- 7. THE GEOTEXTILE FILTER FABRIC SHOULD BE PLACED BETWEEN THE STONE PAD AND THE EARTH SURFACE BELOW THE PAD.
- 8. THE PAD SHALL BE MAINTAINED OR REPLACED WHEN MUD AND SOIL PARTICLES CLOG THE VOIDS IN THE STONE SUCH THAT MUD AND SOIL PARTICLES ARE TRACKED OFF-SITE.
- 9. NATURAL DRAINAGE THAT CROSSES THE LOCATION OF THE STONE PAD SHOULD BE INTERCEPTED AND PIPED BENEATH THE PAD, AS NECESSARY, WITH SUITABLE OUTLET
- 10. WHEN NECESSARY, WHEELS SHALL BE CLEANED PRIOR TO ENTRANCE ONTO PUBLIC
- 11. WHEN WASHING IS REQUIRED, IT SHALL BE DONE ON AN AREA STABILIZED WITH CRUSHED STONE THAT DRAINS INTO AN APPROVED SEDIMENT TRAP OR SEDIMENT
- 4. ROCK BAGS OR SANDBAGS SHALL BE PLACED SUCH THAT NO GAPS ARE EVIDENT. SEE NOTES ERO-03.

TEMPORARY GRAVEL CONSTRUCTION EXIT



EROSION CONTROL DETAILS COMMERCIAL AND INDUSTRIAL FLEX SPACE

TAX MAP 1 PARCEL 44 **BLANCH FARM ROAD GREENVILLE, NEW HAMPSHIRE**

PREPARED FOR AND LAND OF DAVIS VILLAGE PROPERTIES, LLC


P.O. Box 508, New Ipswich, NH, 03071

SCALE: NONE

APRIL 13, 2023

SCALE: N.T.S.

Surveying Φ Engineering Φ Land Planning Φ Permitting Φ Septic Designs



FIELDSTONE LAND CONSULTANTS, PLLC

206 Elm Street, Milford, NH 03055 Phone: (603) 672-5456 Fax: (603) 413-5456 www.FieldstoneLandConsultants.com

PROJ. NO. 1003.02 SHEET: DT-3 PAGE NO. 9 OF 9